BRUHATH BENGALURU MAHANAGA[redacted]DASARAHALLI ZONE

Office of Executi[redacted]

SCHEDUL[redacted]

Name Of Work: Asphalting to roads at Ashok nagar an[redacted]rea in ward no 14 Bagalagunte

Sl. No	Descrption of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Removing and refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	473.40	116.87	
2	Excavation for road, drains and similar works . Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	1814.31	247.55	
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and	Cum	631.80	608.16	
4	Plain cement concrete 1:3:6 mix with crushed stone aggregate 40 m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing complete as per specifications	Cum	152.80	4703.54	
5	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering shuttering cost of materials HOM of	Cum	690.42	7423.71	
6	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required tying with binding wire and anchoring to the adjoining members wherever necessary complete as	Tonne	48.78	77691.85	
7	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete	Nos	3728.00	490.83	
8	Providing and applying spray painting in one coat(excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt,	Sqm	670.80	61.22	
9	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	670.80	89.04	
10	Providing & Laying RCC Drain Slab of 250mm (Date Rate)	Sqm	24.00	5503.05	
11	Providing & Laying RCC Drain Slab of 100mm (Date Rate)	Sqm	1334.00	2318.40	

ವಾ.ವಿ.ಕೆ.ವೆಂಕಟೇಶ್

EXECUTIVE ENGINEER

Scanned with CamScanner

12	Construction of granular sub-base Grading-V as sub base and drainage layers by providing coarse graded crushed stone aggregates of granite / trap / basalt material, mixing in mechanical mix plant at OMC carriage of mixed materials to work site,	Cum	468.59	2094.67	
13	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per	Sqm	2857.40	5.57	
14	Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant	Cum	1005.26	2101.34	
15	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per	Sqm	4370.70	31.16	
16	Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment,	Cum	251.44	6690.24	
17	Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour,	Sqm	11962.60	13.36	
18	Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required grade, level and alignment, rolling with	Cum	239.25	8656.91	
19	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per	Sqm	269.75	477.48	

ಪಂ. ವಿನೋ. ವೆಂಕಟೇಶ್.

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned with CamScanner

BRUHATH BENGALURU MAHANAGARA PALIKE,DASARAHALLI ZONE
Office of Executive Engineer
SCHEDULE -B

Name Of Work: Asphalting to roads at Ashok nagar and surrounding area in ward no 14 Bagalagunte

Sl. No	Descrption of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Removing and refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	473.40	116.87	
2	Excavation for road, drains and similar works . Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	1814.31	247.55	
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and	Cum	631.80	608.16	
4	Plain cement concrete 1:3:6 mix with crushed stone aggregate 40 m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing complete as per specifications	Cum	152.80	4703.54	
5	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering shuttering cost of materials HOM of	Cum	690.42	7423.71	
6	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required tying with binding wire and anchoring to the adjoining members wherever necessary complete as	Tonne	48.78	77691.85	
7	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete	Nos	3728.00	490.83	
8	Providing and applying spray painting in one coat(excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt,	Sqm	670.80	61.22	
9	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	670.80	89.04	
10	Providing & Laying RCC Drain Slab of 250mm (Date Rate)	Sqm	24.00	5503.05	
11	Providing & Laying RCC Drain Slab of 100mm (Date Rate)	Sqm	1334.00	2318.40	

ಎಂ.ವಿಸ್. ವೆಂಕಟೇಶ್.

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
[illegible] Division, Bengaluru-73.

Scanned with CamScanner

12	Construction of granular sub-base Grading-V as sub base and drainage layers by providing coarse graded crushed stone aggregates of granite / trap / basalt material, mixing in mechanical mix plant at OMC carriage of mixed materials to work site,	Cum	468.59	2094.67	
13	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per	Sqm	2857.40	5.57	
14	Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant	Cum	1005.26	2101.34	
15	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per	Sqm	4370.70	31.16	
16	Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment,	Cum	251.44	6690.24	
17	Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour,	Sqm	11962.60	13.36	
18	Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required grade, level and alignment, rolling with	Cum	239.25	8656.91	
19	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per	Sqm	269.75	477.48	

ವಂ.ವಿಸ್.ವೆಂಕಟೇಶ್.

Signature of Contractor

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Executive Engineer
Dasarahalli Division

Scanned with CamScanner